

LIFT-U[®]

A DIVISION OF HOGAN MFG., INC.



HIDDEN ACCESS LIFT PREVENTATIVE MAINTENANCE SCHEDULE

WEEKLY	MONTHLY	6 MONTHS	MANUAL REFERENCE SECTION	LIFT-U[®] HIDDEN ACCESS LIFT PREVENTIVE MAINTENANCE SCHEDULE
				ITEM DESCRIPTION (manual sectional references where applicable)
X			VISUAL	CYCLE LIFT (FULL CYCLE: DEPLOY, RAISE, LOWER AND STOW)
	X	X	VISUAL	INSPECT FLOOR PANELS: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – HINGES FOR LUBE, STRUCTURAL INTEGRITY AND WEAR
	X		VISUAL	C – HINGE MOUNTING BOLTS
	X		VISUAL	D – CYLINDERS FOR LEAKS AND WEAR
	X		VISUAL	E – CYLINDER ROD ENDS FOR WEAR AND LUBE
	X		VISUAL	F – CYLINDER CLEVIS BOLTS
	X		VISUAL	G – FLOOR SCREWS
	X		VISUAL	H – FRONT CLOSEOUT PANEL GUIDES
	X	X	VISUAL	INSPECT LIFT PLATFORM: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – SIDE SKIRT BEARINGS
	X		VISUAL	C – RETAINING STRIPS
	X	X	VISUAL	INSPECT LIFT PLATFORM SIDE PANELS: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – PIVOT PINS AND RETAINING SCREWS
	X		(S5-)	C – RIGHT SIDE PANEL RUBBER BUMPERS
	X		VISUAL	D – ELECTRICAL CABLES FOR CHAFING
	X	X	VISUAL	INSPECT LIFT PLATFORM SIDE PANELS DRIVE ASSEMBLY: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – PIVOT PINS AND RETAINING RINGS
	X		VISUAL	C – CYLINDERS FOR LEAKS AND WEAR
	X		VISUAL	D – HOSES FOR LEAKS AND CHAFING
	X		VISUAL	E – LATCH OPERATION
	X		VISUAL	F – LATCH SPRING
	X		VISUAL	G – RETAINING RINGS
	X		VISUAL	H – MOUNTING CAPSREWS
	X	X	VISUAL	INSPECT LIFT OUTER BARRIER DRIVE ASSEMBLY: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – PIVOT PINS AND WELDS
	X		VISUAL	C – CYLINDERS FOR LEAKS AND WEAR
	X		VISUAL	D – HOSES FOR LEAKS AND CHAFING
	X		VISUAL	E – ELECTRICAL CABLES FOR CHAFING
	X		(S5-)	F – OUTER BARRIER ADJUSTMENT
	X	X	VISUAL	INSPECT OUTER BARRIER: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – PIVOT PINS AND WELDS
	X		VISUAL	C – BULLET GUIDES
	X	X	VISUAL	INSPECT FRONT CLOSEOUT PANELS: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – CLOSEOUT SHOE
	X	X	VISUAL	INSPECT FRONT CLOSEOUT DRIVE ASSEMBLIES: A – STRUCTURAL INTEGRITY
	X		VISUAL	B – PIVOT PINS
	X		VISUAL	C – ACTUATORS
	X		VISUAL	D – ELECTRICAL CABLES FOR CHAFING
	X		(S5-)	E – PANEL ADJUSTMENT

**LIFT-U[®] HIDDEN ACCESS LIFT
PREVENTIVE MAINTENANCE SCHEDULE**

WEEKLY	MONTHLY	6 MONTHS	MANUAL REFERENCE SECTION	ITEM DESCRIPTION (manual sectional references where applicable)
	X X	X	VISUAL VISUAL VISUAL	INSPECT SCISSORS ASSEMBLY: A – STRUCTURAL INTEGRITY B – PIVOT PINS AND ROLLERS C – CYLINDERS FOR LEAKS AND WEAR
	X X X X	X	VISUAL VISUAL VISUAL VISUAL (S5-)	INSPECT STAGE BARRIER ASSEMBLY: A – STRUCTURAL INTEGRITY B – PIVOT PINS C – CYLINDER FOR LEAKS AND WEAR D – CYLINDER ROD ENDS FOR WEAR AND LUBE E – STAGE BARRIER ADJUSTMENT
		X X	VISUAL VISUAL	INSPECT BASE ASSEMBLY: A – STRUCTURAL INTEGRITY B – MOUNTING BOLTS